



1 ENLARGED TRANSIT CENTER HVAC PLAN  
 1/8" = 1'-0" PLAN NORTH

MECHANICAL GENERAL NOTES:  
 A. INDICATES TIE IN POINT. FIELD VERIFY EXACT TIE-IN CONNECTION POINT.

- MECHANICAL KEYED NOTES:
- 24x24 RETURN AIR GRILLES ARE LOCATED IN UPPER MOST DTA WAITING CEILING SERVING PLENUM RETURN.
  - PROVIDE PLASTER FRAME FOR SUPPLY AIR DIFFUSERS IN CYP. BD. CEILING AT THIS LOCATION.
  - RECTANGULAR DUCT DROPS UNDER BEAM AT THIS LOCATION AS REQUIRED.
  - SEE SHEET MP9.02 FOR INJECTION PUMP PIPING DETAIL.



21 W. Superior St., Ste 500 | Duluth, MN 55802 | 218.727.8448



JAMAR COMPANY  
 4701 Mike Colalillo Drive  
 Duluth, MN 55807  
 Mechanical design/build  
 (218) 628-1027  
 (218) 628-1174 FAX  
 www.jamarcorp.com

CLIENT:  
 Duluth Transit Authority

2402 West Michigan Street  
 Duluth, MN 55806

THIS SQUARE APPEARS 1/2" X 1/2" ON FULL SIZE SHEETS

NO.	DATE	ISSUED FOR
1	09-16-14	NO PACKAGE #5
NO.	DATE	REVISION

I HEREBY CERTIFY that this plan, specification or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Signature: *Brent Lommer*  
 Typed or Printed Name: Brent Lommer  
 Date: 09-16-14 Reg. No.: 44202

COPYRIGHT 2012 BY LHB, INC. ALL RIGHTS RESERVED.

PROJECT NAME:  
**DTA - Multimodal Transportation Facility**

228 West Michigan Street  
 Duluth, MN 55802

DRAWING TITLE:  
**MTF ENLARGED TRANSIT CENTER HVAC PLAN**

FILE: 1114000 DTA Multimodal / Base  
 DRAWN BY: DS  
 CHECKED BY: EAT  
 PROJ. NO. 1114000  
 DRAWING NO. **M1.05**